



Introduction


Biology & Engineering

- SOAK is an interdisciplinary project
- Goal: grow Sugar Kelp on frame system

Why Kelp?

- Health Benefits
- Environmental Benefits
- Sustainable aquaculture

Project Design




Design Considerations

- 1. Withstand forces during coastal storms
- 2. Convenience when submerging & raising
- 3. Efficiency growing kelp in a reduced area

Site Conditions

 $u \approx 0.6 m/s$ $u \approx 0.15 m/s$ $T_{avg} \approx 5 s$ $H_{max} \approx 1.6 m$ Flood tide velocity Ebb tide velocity (back eddy) January 2016 Storm 'Jonas' January 2016 Storm 'Jonas'





 $F_D = \rho C_D A_p u^2$

 $u_{max} = \frac{HgT\cosh(k(h+z))}{2}$ $2L \cosh(kh)$

 $u \approx 0.60 m/s$ $u \approx 0.43 m/s$ $u_T = 1.03 \ m/s$


 $F_D = 6300N$ T = 6577NB = 1890N

Max velocity - river current Max particle velocity - waves Total velocity

Resulting drag force Tension in mooring lines Buoyancy

> Acknowledgements: This work is the result of research sponsored in part by the New Hampshire Sea Grant College Program through NOAA grant #NA10OAR4170082, and the UNH Marine Program.

Project S.O.A.K. - Submersible Oceanic Aquaculture of Kelp Angela Sarni, Megan Savoie, Jamie Barton, Hannah Root Advisors: Michael Chambers & Rob Swift



Biology

Materials:

- 2 Nursery Tanks
- PVC Pipe
- Twine
- LED lighting system
- PES nutrients





Methods

- Collect mature sorus tissue
- Spawn & transfer to PVC
- 12 hour light cycle
- Weekly nutrients, 4 weeks
- Continue growth in ocean
- Transfer from spools to frame








Fabrication

- Cut & transport pipes to site
- Fused pipes into frame
- Drilled holes in pipes
- Assembled mooring system

Deployment



Conclusion

- Cohesive interdisciplinary team
- End goal accomplished
- Nature can dictate timeline
- Kelp growth monitored
- Future work prospects







3/24 - Snowstorm • Seeded lines • Deployed mooring system

3/28 - Cloudy Attached weights & buoys on beach Towed frame off beach Tied frame to raft in bay temporarily

3/30 - Sunny Towed frame to site Attached pre-seeded lines • Attached frame to mooring Seeded remaining lines